

## Kerb Remediation and Traffic Island Crack Repair



### The Project

Client: Goodstart Early Learning Boronia Heights

Scope: Kerb Remediation Traffic Island  
Crack Repair

The outcome sought by the Client was to remediate the cracked concrete and reinstate the kerb following damage caused by a delivery truck.

#### Before



### The Scope

- Clean and prepare the concrete crack and cracked kerbing pieces by mechanical grinding
- Reposition the broken pieces to original position
- Install 16mm booker rod pins to secure the kerbing to the base slab
- Apply gap filling epoxy construction adhesive to the kerb/island interface and pin installation penetrations
- Apply sealant to any visible cracks
- Repaint kerbing to match
- Comply with site specific safety requirements

### The Outcome



## Kerb Remediation and Traffic Island Crack Repair

During



After

